

**F.No : 1-83/19-20/ST****Date : 04.03.2020****LIMITED TENDER ENQUIRY**

Sub: Limited tender for **“Supply and Installation of Biofloc Technology Unit at MES of CIBA, Kovalam Post, Muttukadu Chennai-613112, Tamil Nadu”** - Reg.

Please furnish your quotation in the enclosed schedule for the work of **“Supply and Installation of Biofloc Technology Unit at MES of CIBA, Kovalam Post, Muttukadu Chennai-613112, Tamil Nadu”** as per the specification. Furnishing of the quotation is governed by the following terms and conditions.

1. The quotation should be submitted in a sealed cover and should reach this office on or before 09.03.2020- 15.00 hrs addressed to the Director, Central Institute of Brackish water Aquaculture, No.75 Santhome High road, Raja Annamalai Puram, Chennai-600 028. The quotation received after the scheduled time will not be considered at all.
2. The envelope consisting the quotation should be superscripted as **“Supply and Installation of Biofloc Technology Unit at MES of CIBA, Kovalam Post, Muttukadu Chennai-613112, Tamil Nadu”**. The quotation without superscription is liable to be rejected.
3. The right to accept the rates and bidding the work based on the quality and reputation of the firms rests with the DIRECTOR, CIBA and it cannot be challenged. The DIRECTOR, CIBA reserves right to accept or reject any one or all the quotation without any reason.
4. Quotation may be furnished for **“Supply and Installation of Biofloc Technology Unit at MES of CIBA, Kovalam Post, Muttukadu Chennai-613112, Tamil Nadu”** as per the Annexure (**PRICE BID**)
5. No advance and any part payment will be made for this work.
6. During executing of work any loss/Hazard due to any reason for the men and materials will be borne by the contractor. The Institute will not be responsible for any loss or damage /Hazard
7. While executing the work, the executing agency is fully responsible for any damage to Institute materials and the same may be replaced (including materials & labour charges for the replacement) by the Contractor at his own cost.
8. The work should be completed to the satisfaction of the authority concerned.

9. The contractor has to visit the site and get acquainted with the place and accordingly the items/units has to be quoted.
10. The rates are to be quoted as per the Specifications , no change in rates will be accepted after submission of the quotations.
11. For inspection of site, Dr.Akshaya Panigrahi ( Phone No:04424610565 Ext-412/ 09025739499), may please be contacted between 10.00 hrs to 16.00 hrs on all working days.
12. Payment will be made after completion of the work to the satisfaction of the authority concerned.
13. Experience / work completed certificates.

**The Director,  
Central Institute of  
Brackishwater Aquaculture,  
No.75.Santhome High Road,  
R.A.Puram,  
Chennai – 600 028.**

### **SPECIFICATIONS**

**Name of the work: Setting up & fixing of one Biofloc Unit comprising of six 20 tons circular tank units with proper central drainage and aeration facilities**

<b>S.No</b>	<b>Description</b>	<b>Quantity</b>	<b>Per</b>
1	20 tons circle tanks ( 1 inch B class Jindal/TATA/equivalent round pipes , 1 mm HDPE imported liner & poly locks)	6	No s
2	19.3*13.2 mtrs Shade net structure with 1 1/2 inch GI pipe polls , 1 1/4 inch GI top structure and Net Door)	1	No s
3	70% Shade net imported	2	Rolls
4	50% Shade net imported	2	Rolls
5	2 1/2 inch PVC pipes 6 kg pipes	5	Bars
6	2 1/2 inch PVC L Bends	6	No s
7	2 1/2 inch PVC coupling	3	No s
8	2 1/2 inch PVC Ball valves	6	No s
9	PVC solvent	0.5	Lt
10	26 Gi polls digging (3mtr length) & 3/3 cubic feet sumps construction	2	No s
11	Circular tanks (10 inch width 1 feet height brick round wall , Tanks installation and center drainage work).	6	No s
12	Ground leveling work (20 mtr * 20 mtr)	1	No s
13	Movement 1 1/2 mtr PVC grid	12	No s
14	Aero tube	300	Meter
15	PVC pipe line from the blower to all the Tanks.	1	Meter
16	PVC pipe line from the water motor to all the tanks	1	Meter
17	1 1/2 mtr PVC grids with weights	75	sets
18	Grids connecting lateral 16 mm pipe and fittings all the tanks.	6	Tanks

**ANNEXURE**

PRICE BID		
Sl.No	Item Description	Amount
1.	Setting up & fixing of one Biofloc Unit comprising of six 20 tons circular tank units with proper central drainage and aeration facilities	
2.	GST	
Total		
(Rupees_____)		

केन्द्रीय खारा जलजीव पालन अनुसंधान संस्थान (भारतीय कृषि अनुसंधान परिषद)  
#75, संथोम हाई रोड, राजा अण्णामलैपुरम, चेन्नई - 600028, तमिलनाडु, भारत



Phone: EPBX: +91 44 24618817, 24616948, 24610565

Fax: +91 44 24610311

Email: director.ciba@icar.gov.in, director@ciba.res.in